No.	Item of work	Unit	Quantity
	Central Dome—concld.		
12	Stucco work in plastering	S. ft.	329
13	Cement concrete work dome portion including plastering both sides including scaffolding charges.	C. ft.	1,181
14	Ornamental wooden brackets with railing complete painting, etc., as per design.	R. ft.	100
15	Stone brackets, large, and plastered over below dome	No.	8
16	Masonry ornamental small towers at the foot of the dome, complete	"	4
17	Ornamental ocesting above small passages	R. ft.	50
18	Do leaf work with cement bottom of dome	"	50
19	Do cornice do 9"	L. S.	
20	Do plaster work, between the brackets below dome inside	"	
21	Large finial at top of dome	R. ft.	41
22	Cornice ½" heave up inside	No.	4
23	Ornamental pendants below small projected pillasters	"	24
24	Preparing corinthian cap for pillasters in front of tower	"	24
25	Do froming, bottom of pillasters	R. ft.	416
26	Cast iron rain-water pipes	Sq.	32·17
27	Plastering with chunam	Cwt.	11
28	Steel girders circular, hoisting painting, etc., complete	"	24
29	Wrought iron angle ribs and rivets		
	End towers 4 in number.		
	N.B.—Quantities noted are for one tower only.		
1	Saraki stone pillar, dressed with base and capital and shaft, etc., complete	No.	8
2	Burnt brick in chunam, foliated	C. ft.	400
3	Archwork, burnt brick in chunam, foliated	"	81
4	Armoured concrete	"	144
5	Steel girders	Cwt.	756
6	Plastering with chunam	Sq.	1,001
7	Armoured concrete slabs	S. ft.	144
8	Cuddappah slab lovey and chunam plastered over and ornamental brackets, complete.	R. ft.	56
9	Cornice below lovey, 4½"	"	95
10	Ornamental parapet wall top of lovey cornice	"	40
11	Rosettes at haunches of arches	No.	16
12	Ornamental stucco work to bottom parapet wall	S. ft.	114
13	Masonry finials, complete	No.	1
	Foundation and basement for the extra length of the wings as layout.		
1	Earthwork excavation	Cyd.	50
2	Earth-filling, including watering and tamping	"	103
3	Extra-earth filling including carting, watering and tamping	"	53
4	Granite stone jelly in mortar foundation, using stone already collected for the purpose.	C. ft.	450
5	Granite stone hammer, dressed in mortar foundation using stone already collected for the purpose.	"	1,065
6	Coursed granite stone masonry in mortar with faces, nicely dressed for basement.	"	392
7	Bebobetta stone slabs, 7" thick, over basement	S. ft.	110
8	Dressing cornice to face of Bebobetta stone slabs, over basement including top dressing.	R. ft.	40
9	Storm water drain around the building with Cuddappah slabs and cement as per design.	"	40
10	Forming cornice bottom of the basement as per basement top cornice, including inside court yard cornice.	S. ft.	20

GURU RAO SIRSI,
Assistant Engineer,
Head quarter Range, Mysore.

KADUR DIVISION.

Dated 14th July 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 5th August 1918, for constructing Police Lines at Bommenahalli, Narasimharajapura Sub-Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 and 5 P.M., office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Police Lines at Bommenahalli, Narasimharajapura Sub-Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of detailed quantities for constructing Police Line at Bommenahalli in Narasimharajapura Sub-Taluk.

No.	Items of work	Per	Quantity	
			Single block	Additional block
1	Earthwork excavating and filling	C. yd.	25	113
2	Concrete in chunam	C. ft.	230	1,017
3	Rough size stone in clay	"	545	2,281
4	Burnt brick in clay	"	449	1,960
5	Burnt brick in chunam	"	134	592
6	Reinforced concrete slabs	S. ft.	445	179
7	Plastering with chunam	Sqr.	13·33	48·52
8	Coping with brick in chunam and plastering	R. ft.	39	172
9	White and colourwashing	Sqr.	13·33	48·52
10	Honney wood battened doors with iron clamps and pointing, etc.	S. ft.	845	260
11	Honney wood battened windows with iron bars and painting, etc.	"	875	35
12	Honney wood ventilators with iron bars and shutter, etc.	"	375	15
13	Honney or Naudi wood wrought and put up with wood oiling	C. ft.	17·71	90·00
14	Roofing with 1st Class Mangalore tiles on teak reepers with wood oiling.	Sqr.	4·01	17·15
15	Mangalore ridge tiles sit in morter and pointed with cement	R. ft.	11	89
16	Honney wood eave board ornamental with painting	"	45	231
17	Chunam borders	"	12	20
18	Flooring with concrete and plastering with chunam	C. ft.	57	236
19	Providing smoke escape in the kitchen	No.	1	4
20	"U" shaped concrete drain and plastering with cement	R. ft.	23	92
21	Gravelling the compound	C. yd.	2	8
22	Providing out-let pipes for kitchen and latrine	No.	2	8
23	Constructing seats and drains in the latrine	L. S.	Rs.	Rs.
24	Clearing site and levelling ground and tarring	L. S.	Rs.	Rs.
25	Chunam pointing	Sqr.	0·22	1·30
26	Tarring	L. S.	Rs.	Rs.
27	Finials and pendants	L. S.	Rs.	Rs.

K. PONNAPPA,
Executive Engineer.

DISTRICT, MUNICIPAL AND LOCAL BOARDS.

BANGALORE CITY MUNICIPALITY.

Notice dated 8th July 1918.

Sealed tenders for supplying the following articles of furniture will be received by the undersigned in the Municipal Office up to 31st July 1918.

2. Each tender must be accompanied by a deposit of Rs. 25 in cash or in currency notes and be superscribed "Tender for the supply of furniture."

3. Information regarding design, etc., may be had at the Municipal Office, during office hours.

4. The tender must be accompanied by a statement showing the rates at which the different items specified below will be executed.

5. The final acceptance of the tender will rest with the undersigned, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days after the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money forfeited.

7. The name of the successful tenderer whose tender has been accepted, will be duly notified to him.

8. On acceptence of one or more tenders, the earnest money of rejected tenderers will be returned.

9. The articles should be delivered at the office on or before the end of September 1918.